

ADDENDUM NO. 01

CITY OF FAIRHOPE

**Bid No. 025-13 Upgrade Multi-media Equipment Giddens Conference Center FPL
for**

CITY OF FAIRHOPE, AL

The bid documents for this Bid shall be amended, revised and changed in the following particulars:

QUESTIONS FROM POTENTIAL BIDDERS:

Question No. 1:

The advertisement states "All prospective CONTRACTORS shall have a representative present at the Pre-bid Meeting". Is the meeting mandatory?

Answer to Question No. 1

The meeting was not mandatory. The word "shall" should read 'may'.

Question No. 2:

The existing speakers do not have power at the speaker mounts. Will there be power provided there for the new speakers that require such?

Answer to Question No. 2

Yes.

Question No. 3:

Is the screen surface mount, or recessed?

Answer to Question No. 3

The screen is a recessed model.

CORRECTION

Remove: The first page of ITEM III BID RESPONSE FORM.

Insert: New first page of ITEM III BID RESPONSE FORM rev1 (see attached).

CORRECTION

Remove: page 21 under Scope and Specifications.

Insert: New page 21 under Scope and Specifications rev1 (see attached).

ITEM III

BID RESPONSE FORM rev1

CITY OF FAIRHOPE

DATE: ____/____/____

Bid No.: 025-13 Upgrade Multi-Media Equipment Giddens Conference Center FPL
Project No: PW014-13 Upgrade Multi-Media Equipment Giddens Conf Center FPL

<u>Video Projection and Audio System Update Amount</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Units</u>	<u>\$ Per Unit</u>	<u>Extended \$</u>
Digital Projection M-Vision cine 400-3D (5500 lumens) w/2.4-40:1 High Brightness	_____	_____	1	_____	_____
Projector Mount cantilever	_____	_____	1	_____	_____
Stewart Filmscreens Motorized 16:9 aspect ratio screen 14' wide	_____	_____	1	_____	_____
Yamaha Aventure CX-A5000AV surround preamplifier w/balance audio outputs	_____	_____	1	_____	_____
Allen & Heath ZED12FX mixing board	_____	_____	1	_____	_____
Oppo BCP-103 single disc universal player with 3D	_____	_____	1	_____	_____
QSC K12 active monitors	_____	_____	2	_____	_____
QSC KSUB active subwoofer	_____	_____	2	_____	_____
Rane AC22S stereo active	_____	_____	1	_____	_____
Strong 21 U rolling rack with side panels and four (4) fixed utility shelves	_____	_____	1	_____	_____
SurgeX XS115, 8-outlet 15 Amp rack mount surge eliminator	_____	_____	1	_____	_____
DLI Web Power Switch 7	_____	_____	1	_____	_____
Ethereal EHD-HD1M 1 meter active HDMI signal restoring cable (equipment > extenders)	_____	_____	1	_____	_____
Ethereal HD-BaseT extender system (receiver>display)	_____	_____	1	_____	_____
RTI XP-6 control processor	_____	_____	1	_____	_____
RTIPanel license for iPad	_____	_____	1	_____	_____
Apple iPad mini, 16GB, WiFi only	_____	_____	1	_____	_____
Binary IR emitters	_____	_____	4	_____	_____
Materials (writing, j-boxes, fasteners, etc)	_____	_____	1	_____	_____
<u>Network</u>					
Gigabit wired router (main rack)	_____	_____	1	_____	_____
Eight port Gigabit Ethernet switch	_____	_____	1	_____	_____
High performance 2x2 MiMo WiFi Access Point (main rack)	_____	_____	1	_____	_____
Binary 3m Ethernet jumper	_____	_____	1	_____	_____
Binary 1m Ethernet jumper	_____	_____	4	_____	_____
<u>Labor+Totals</u>					
Programming, hourly	_____	_____	—	_____	_____
Remote network configuration, hourly	_____	_____	—	_____	_____
Installation labor, day rate, two (2) Techs	_____	_____	—	_____	_____
Installation labor, day rate, one (1) Lead Tech	_____	_____	—	_____	_____

We propose to meet or exceed the above specifications for the sum of: \$ _____
The Contractor agrees to complete all the work within THIRTY (30) calendar days from date given in the Notice to Proceed (NTP) unless other arrangements are approved by the Project Manager.
 Receipt of the following Addenda to these documents is hereby acknowledged by the undersigned (bidder to complete below):

wired and/or wireless microphone inputs for a minimum of three microphones, as well as line level audio inputs to accommodate source devices. The de-mark for the audio system shall be located within 5' of the control panel.

Control system: The iPad/iPad-Mini shall be mounted in the wall so as to be conveniently available at any time the system needs to be controlled. Access to the user interface shall be password protected. The interface shall provide real-time feedback to the user as to the current status of the projector, screen and source(s). If a manual input is initiated at one of the external devices, the user interface shall reflect that change in status with no input from the user. The control system shall be capable of communicating with devices via TCP/IP, RS-232, IR, voltage sync sensing and/or contact closure. The only exception to this requirement is guest- provided sources such as laptop(s) connected at the podium. The control system master processor shall be rack-mounted

TECHNICAL SPECIFICATIONS

Video Projection and Audio System Update

	UNIT
Digital Projection M-Vision cine 400-3D (5500 lumens) w/2.4-40:1 High Brightness Projector Mount cantilever	Digital Projection 1
Stewart Filmscreens Motorized 16:9 aspect ratio screen, 14' wide	Strong 1
Yamaha Aventage CX-A5000AV surround preamplifier w/balance audio outputs	Stewart Filmscreens 1
Allen & Heath ZED12FX mixing board	Yamaha 1
Oppo BCP-103 single disc universal player with 3D	Allen & Heath 1
QSC K12 active monitors	Oppo 1
QSC KSUB active subwoofer	QSC 2
Rane AC22S stereo active	QSC 2
Strong 21 U rolling rack with side panels and four (4) fixed utility shelves	RANE 1
SurgeX XS115, 8-outlet 15 Amp rack mount surge eliminator	RTI 1
DLI Web Power Switch 7	SurgeX 1
Ethereal EHD-HD1M 1 meter active HDMI signal restoring cable (equipment to extenders)	Digital Loggers 1
Ethereal HD BaseT extender system (receiver>display)	Ethereal 1
RTI XP-6 control processor	RTI 1
RTiPanel license for iPad	RTI 1
Apple iPad mini, 16GB, WiFi only	Apple 1
Binary IR emitters	Binary 4
Materials (mounts, wiring, j-boxes, fasteners, etc)	BSUN 1
<u>Network</u>	
Gigabit wired router (main rack)	MikroTik 1
Eight port Gigabit Ethernet switch	Netgear 1
High performance 2x2 MiMo WiFi Access Point (Main Rack)	Ubiquiti 1
Binary 3m Ethernet jumper	Binary 1
Binary 1m Ethernet jumper	Binary 4
<u>Labor+Totals</u>	
Programming, hourly	
Remote network configuration, hourly	
Installation labor, day rate, two (2) Techs	
Installation labor, day rate, one (1) Lead Tech	

END OF SCOPE AND SPECIFICATIONS rev1

Bidders are to sign and include signed Addendum No.1 with submitted bid documents.

Acknowledged:

Company

By _____

Daniel P. Ames Purchasing Manager City
of Fairhope Posted: 08-07-13

END ADDENDUM NO. 1